

## WISCONSIN CONSTRUCTION SPECIFICATION

### 7. MOBILIZATION AND DEMOBILIZATION

#### 1. SCOPE

The work consists of the mobilization and demobilization of the Contractor's forces and equipment necessary for performing the work required.

#### 2. EQUIPMENT AND MATERIAL

Mobilization shall include:

- All activities and associated costs for transportation of the Contractor's personnel, equipment, and operating supplies to the site;
- Establishment of offices, buildings, and other necessary general facilities for the Contractor's operations at the site
- Premiums paid for performance and payment bonds including coinsurance and reinsurance agreements as applicable
- Construction and maintenance of haul roads and equipment parking areas
- Other job related items

Demobilization shall include:

- All activities and costs for transportation of personnel, equipment, and supplies not utilized in the project from the site
- Disassembly, removal, and site cleanup of offices, buildings, and other facilities assembled on the site.
- Repair of access roads, temporary haul roads, and equipment parking areas leaving the project site in the same or better condition than at the start of the project.
- General cleanup and house keeping needed to restore a neat and orderly project site.

Access to the site, equipment parking, and staging areas are limited to that shown on the drawings or as approved by the technician.